

AD-A072 805

D'APPOLONIA CONSULTING ENGINEERS INC PITTSBURGH PA  
NATIONAL DAM INSPECTION PROGRAM. WOLF CREEK DAM (LAKE RENE). ND--ETC(U)  
JUN 79


F/G 13/2

DACW31-79-C-0014


NL

UNCLASSIFIED

| OF |  
AD  
A072805



END  
DATE  
FILMED  
9-79  
DDC



MICROCOPY RESOLUTION TEST CHART  
NATIONAL BUREAU OF STANDARDS-1963-A

Wolf Creek Dam (Lake Rene).  
NDI I.D. Number PA-748. DER I.D.  
Number 17-108. Ohio River Basin,  
Wolf Creek, Clearfield County,  
Pennsylvania. Phase I Inspection Report.

PREFACE

DDC  
RECEIVED  
AUG 17 1979  
C

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Department of the Army, Office of Chief of Engineers, Washington, D.C. 20314.

The purpose of a Phase I investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon visual observations and review of available data. Detailed investigation and analyses involving topographic mapping, subsurface investigations, material testing, and detailed computational evaluations are beyond the scope of a Phase I investigation; however, the inspection is intended to identify any need for such studies which should be performed by the owner.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of the dam depends on numerous and constantly changing internal and external factors which are evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through frequent inspections can unsafe conditions be detected and only through continued care and maintenance can these conditions be prevented or corrected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the spillway design flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. The spillway design flood provides a measure of relative spillway capacity and serves as an aid in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

The assessment of the conditions and recommendations was made by the consulting engineer in accordance with generally and currently accepted engineering principles and practices.

79 08 15 077



PHASE I REPORT  
NATIONAL DAM INSPECTION PROGRAM

NAME OF DAM: Wolf Creek Dam  
STATE LOCATED: Pennsylvania  
COUNTY LOCATED: Clearfield  
STREAM: Wolf Run, a secondary tributary of Sandy Lick Creek  
DATE OF INSPECTION: April 4 and May 4, 1979

ASSESSMENT: Based on the evaluation of the existing conditions, the condition of Wolf Creek Dam is considered to be good.

Several wet areas were observed on the downstream slope and along the toe of the embankment. These areas should be periodically observed and remedial work performed if conditions worsen.

Wolf Creek Dam is one of the three dams which impound Lake Rene. The spillways associated with this dam and Galion Bay Dam constitute the flood discharge facilities for Lake Rene. Lake Rene Dam has no spillway structures.

The flood discharge capacity of Lake Rene was evaluated according to the recommended procedure and was found to pass 90 percent probable maximum flood (PMF); therefore, according to the recommended criteria, the flood discharge capacity of Lake Rene was classified to be inadequate.

The following recommendations should be implemented on a continuing basis:

1. The wet areas located along the downstream face and the toe of the embankment should be periodically observed. Necessary remedial work should be performed if the extent of the wet areas increases or seepage and sloughing conditions develop.
2. Around-the-clock surveillance should be provided during unusually heavy runoff and a formal warning system should be developed to alert the downstream residents in the event of emergencies.
3. Small trees on the upstream face of the dam should be removed.

Accession For	<input checked="" type="checkbox"/>
NTIS GRA&I	<input type="checkbox"/>
DDC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification for the	<input type="checkbox"/>
By	<input type="checkbox"/>

*on file*

79 00 77 A

4. The dam and appurtenant structures should be inspected regularly and necessary maintenance should be performed.



*Lawrence D. Andersen*

Lawrence D. Andersen, P.E.  
Vice President

June 25, 1979

Date

Approved by:


*James W. Peck*

JAMES W. PECK  
Colonel, Corps of Engineers  
District Engineer

27 July 1979

Date

WOLF CREEK DAM  
NDI I.D. NO. PA-748  
APRIL 4, 1979



Upstream Face



Downstream Face



## TABLE OF CONTENTS

	<u>PAGE</u>
SECTION 1 - PROJECT INFORMATION	1
1.1 General	1
1.2 Description of Project	1
1.3 Pertinent Data	2
SECTION 2 - DESIGN DATA	5
2.1 Design	5
2.2 Construction	7
2.3 Operation	7
2.4 Other Investigations	7
2.5 Evaluation	7
SECTION 3 - VISUAL INSPECTION	9
3.1 Findings	9
3.2 Evaluation	10
SECTION 4 - OPERATIONAL FEATURES	11
4.1 Procedure	11
4.2 Maintenance of the Dam	11
4.3 Maintenance of Operating Facilities	11
4.4 Warning System	11
4.5 Evaluation	11
SECTION 5 - HYDRAULICS AND HYDROLOGY	12
5.1 Evaluation of Features	12
SECTION 6 - STRUCTURAL STABILITY	13
6.1 Evaluation of Structural Stability	13
SECTION 7 - ASSESSMENT AND RECOMMENDATIONS/PROPOSED REMEDIAL MEASURES	14
7.1 Dam Assessment	14
7.2 Recommendations/Remedial Measures	14

**TABLE OF CONTENTS**  
**(Continued)**

**PLATES**

- APPENDIX A - CHECKLIST, VISUAL INSPECTION, PHASE I**
- APPENDIX B - CHECKLIST, ENGINEERING DATA, DESIGN, CONSTRUCTION,  
OPERATION AND HYDROLOGIC AND HYDRAULIC, PHASE I**
- APPENDIX C - PHOTOGRAPHS**
- APPENDIX D - CALCULATIONS**
- APPENDIX E - REGIONAL GEOLOGY**

PHASE I REPORT  
NATIONAL DAM INSPECTION PROGRAM  
WOLF CREEK DAM  
NDI I.D. NO. PA-748  
DER I.D. NO. 17-108

SECTION 1  
PROJECT INFORMATION

1.1 General

a. Authority. The inspection was performed pursuant to the authority granted by The National Dam Inspection Act, Public Law 92-367, to the Secretary of the Army, through the Corps of Engineers, to conduct the inspections of dams throughout the United States.

b. Purpose. The purpose of this inspection is to determine if the dam constitutes a hazard to human life or property.

1.2 Description of Project

a. Dam and Appurtenances. Wolf Creek Dam consists of an earth embankment approximately 1050 feet long with a maximum height of 34 feet from the downstream invert of the outlet works conduit and a crest width of 40 feet. Wolf Creek Dam is one of the three dams which impound Lake Rene. The other two dams are Galion Bay Dam, located at the south side of Lake Rene, and Lake Rene Dam, located on the east side of the reservoir. Lake Rene Dam, which was constructed in 1955, was the original dam at the site. Wolf Creek Dam and Galion Bay Dam were constructed in 1971 in conjunction with the enlargement of Lake Rene.

The flood discharge facilities for Lake Rene consist of primary and emergency spillways associated with Wolf Creek and Galion Bay dams. The Wolf Creek Dam flood discharge facilities are comprised of a drop inlet primary spillway located at the center of the embankment and an emergency spillway on the left abutment (looking downstream). The primary spillway structures consist of a single-stage reinforced concrete riser, a 36-inch-diameter reinforced concrete conduit, and a plunge pool at the downstream end of the outlet pipe. The emergency spillway is an 130-foot-wide trapezoidal earth channel excavated into the left abutment. The reservoir drainpipe for the dam consists of a 15-inch steel pipe extending from the upstream toe of the dam to the drop inlet structure. Flow through the reservoir drainpipe is controlled by a manually operated sluice gate located in the drop inlet structure. The reservoir drainpipe constitutes the emergency drawdown facility for the reservoir.



b. Location. The dam is located on Wolf Run, a secondary tributary of Sandy Lick Creek, approximately three miles north of DuBois in Sandy Township, Clearfield County, Pennsylvania (Plate 1).

Downstream from the dam, Wolf Run follows a 1000- to 1500-foot wide valley for approximately 3-1/2 miles where it flows under U.S. Route 219. It then turns south and follows a course parallel to Route 219 for three miles where it joins Sandy Lick Creek approximately 1/2 mile south of Falls Creek, Pennsylvania. The first three-mile reach of Wolf Run downstream from the dam is uninhabited. Two commercial buildings and one police station are located in the area where Wolf Run flows under Route 219. It is estimated that failure of the dam would cause large loss of life and property damage along Route 219 and further downstream in the town of Falls Creek.

c. Size Classification. Intermediate (based on 34-foot height and 6750 acre-feet storage capacity).

d. Hazard Classification. High.

e. Ownership. Treasure Lake of Pennsylvania, Inc. (address: Mr. James R. Farrer, Director of Development, Treasure Lake of Pennsylvania, Inc., P.O. Box 687, DuBois, Pennsylvania 15801).

f. Purpose of Dam. Recreation.

g. Design and Construction History. The dam was designed by R. M. Keddal and Associates, Inc., of Bethel Park, Pennsylvania, and Engineering Mechanics, Inc., of Pittsburgh, Pennsylvania in 1969. The dam was constructed by the Canton Development Company of DuBois, Pennsylvania, with completion in 1971.

h. Normal Operating Procedure. The reservoir is normally maintained at Elevation 1662.5, the uncontrolled primary spillway crest elevation for both Wolf Creek and Galion Bay dams. The inflow occurring when the lake is at or above the primary spillway level is discharged through the primary and emergency spillways of the Wolf Creek and Galion Bay dams.

### 1.3 Pertinent Data

a. <u>Drainage Area</u>	4.4 square miles
b. <u>Discharge at Dam Site (cfs)</u>	
Maximum known flood at dam site	Unknown
Outlet conduit at maximum pool	20
Gated spillway capacity at maximum pool	N/A



Ungated spillway capacity at maximum pool <sup>(1)</sup>	3844
Total spillway capacity at maximum pool <sup>(1)</sup>	3844

c. Elevation (USGS Datum) (feet)

Top of dam	1670 (as designed); 1670.7 (measured low spot)
Maximum pool	1670.7
Normal pool	1662.5
Upstream invert outlet works	1643
Downstream invert outlet works	1637
Streambed at center line of dam	1636+
Maximum tailwater	Unknown

d. Reservoir Length (feet)

Normal pool level	10,000
Maximum pool level	10,000

e. Storage (acre-feet)

Normal pool level	3700
Maximum pool level	6750

f. Reservoir Surface (acres)

Normal pool level	310
Maximum pool level	360

g. Dam

Type	Earth
Crest length	1050 feet
Height	34 feet
Top width	40 feet
Side slopes	3H:1V both upstream and downstream slopes
Zoning	Yes
Impervious core	Yes
Cutoff	Yes
Grout curtain	No

h. Regulating Outlet

Type	15-inch reservoir outlet pipe
Length	50+ feet

<sup>(1)</sup> Wolf Creek Dam spillway only.

Closure

Access

Retaining facilities

Sluice gate at  
drop inlet  
structure  
Through drop  
inlet structure  
Sluice gate

1. Spillway

Primary

Emergency

Type

Drop inlet

Trapezoidal earth  
channel

Length

18 feet

130 feet

Crest elevation

1662.5

1664.5

Gates

None

None

Upstream channel

Lake

Trapezoidal earth  
channel

Downstream channel

36-inch outlet  
conduit

Trapezoidal earth  
channel

SECTION 2  
DESIGN DATA

2.1 Design

a. Data Available. The available information was provided by the Commonwealth of Pennsylvania, Department of Environmental Resources (PennDER).

(1) Hydrology and Hydraulics. The available information consists of design and freeboard hydrographs and associated flood routings.

(2) Embankment. Available information consists of design drawings, construction specifications, engineer's report and calculations.

(3) Appurtenant Structures. Available information includes design drawings.

b. Design Features

(1) Embankment

a. As designed, the dam (Plate 2) is a zoned embankment (Plate 3) with an impervious core extending through a cutoff trench to the top of rock and an internal drainage system beneath the downstream slope. Two zones were identified. The first zone was identified as an impervious zone and forms the core of the embankment. The second zone was a semi-impervious zone and constitutes the shell sections of the embankment. The impervious core is trapezoidal in cross section and starts at a level five feet below the crest of the dam and extends through the cutoff trench to the top of rock. The internal drainage system consists of a trench drain along the downstream toe of the embankment. The trench drain, as shown in Plate 3, is equipped with a perforated pipe. The trench drainpipe discharges into the outlet works discharge channel.

b. The dam was designed to have a 3H to 1V slope on both the upstream and downstream faces, except for the portion of the upstream slope below the bench at Elevation 1658 which was designed to have a 5H to 1V slope.



- c. As shown in Plate 4, the subsurface investigation for the dam consisted of four borings extending into rock and six shallow auger borings. The subsurface profile was described as 6 to 24 feet of medium stiff to very stiff colluvial soils underlain by medium dense to very dense alluvial deposits. The foundation rock was described as sandstone underlain by shale and sandstone layers. While the upper sandstone layer was described as highly weathered, the second sandstone seam was described as moderately broken to massive.

(2) Appurtenant Structures. The appurtenant structures of the dam consist of a drop inlet primary spillway and an emergency spillway. The primary spillway structures include a single-stage reinforced concrete riser and a 36-inch-diameter reinforced concrete conduit through the embankment terminating at a plunge pool at the downstream toe of the dam (Plate 4). A 15-inch steel pipe from the upstream toe of the dam discharging into the drop inlet structure constitutes the reservoir outlet facilities. Flow through the reservoir outlet pipe is controlled by a sluice gate at the drop inlet structure. The spillway conduit is encased in concrete and is equipped with reinforced concrete cutoff collars through the embankment.

The emergency spillway is a trapezoidal earth channel excavated into the left abutment (Plate 2). Plate 5 illustrates the longitudinal profile and cross sections of the emergency spillway channel. The bottom width of the trapezoidal channel is 130 feet with side slopes of 2H to 1V. A 30-foot-wide level section at Elevation 1664.5 in line with the axis of the embankment constitutes the control section of the spillway. Details of the primary spillway drop inlet structure are shown on Plate 6.

c. Design Data

(1) Hydrology and Hydraulics. An undated report entitled, Wolf Creek Dam for Treasure Lake of Pennsylvania, Inc., prepared by R. M. Keddal and Associates, Inc., and Engineering Mechanics, Inc., includes available hydrology and hydraulic analyses for the dam. It appears that although some calculations were performed according to the Soil Conservation Service (SCS) procedures, the emergency spillways of Galion Bay and Wolf Creek dams which constitute the flood discharge facility for Lake Rene were sized according to Pennsylvania design criteria in effect at the time ("C" curve). The combined discharge capacity of Galion Bay and Wolf Creek dams spillways was reported to be 5000 cfs with no freeboard.

(2) Embankment. Available information indicates that apparently the dam was designed based on very limited engineering analyses. The engineer's report indicates that the laboratory testing for the borrow

materials consisted of classification, compaction, and permeability tests. Borrow material for the impervious core was described as brown sandy silt and red silty clay. The permeability of this material was reported to be in the range of  $10^{-6}$  cm/sec. The engineer's report included no reference to laboratory soil strength testing. It appears that the stability calculations were based on assumed soil strength parameters. The assumed effective strength parameters were internal friction angle, 25 degrees; cohesion, 200 pounds per square foot. The computed factors of safety were 2.1 for the downstream slope under steady-state seepage conditions and 1.2 for the upstream slope under rapid drawdown conditions.

(3) Appurtenant Structures. It appears that the design of the appurtenant structures was based on standard SCS designs.

2.2 Construction. Available information consists of various construction progress reports. No as-built drawings were available. One design modification was noted. During foundation excavation for the outlet conduit, top of rock was not encountered at the anticipated elevation of 1640. Additional borings drilled indicated top of rock to be at Elevation 1609. Soils below Elevation 1640 were classified as overconsolidated colluvium. The engineer's recommendation was to found the outlet works at Elevation 1640. The engineer reported that settlement of the outlet works founded on the colluvium would be negligible. Available records indicate that the dam was constructed under the supervision of Engineering Mechanics, Inc.'s field representative.

Available information indicates no post-construction changes.

2.3 Operation. No records of operation have been kept.

2.4 Other Investigations. None reported.

## 2.5 Evaluation

a. Availability. Available information was obtained from PennDER.

b. Adequacy

(1) Hydrology and Hydraulics. Available information indicates that the spillway was designed in conformance with Pennsylvania spillway design criteria applicable at the time of design. Only the design capacity is reported, therefore, this information is not adequate to assess the conformance of the spillway capacity in accordance with current spillway design criteria.

(2) Embankment. The dam was apparently designed based on limited subsurface investigation and engineering analyses. Laboratory testing consisted of classification, compaction, and permeability tests. No reference to strength testing was found. It appears that the stability of the dam was analyzed based on assumed soil strength parameters.

(3) Appurtenant Structures. Review of the design drawings indicates that as designed no significant design deficiencies existed that should affect the overall performance of the appurtenant structures.



SECTION 3  
VISUAL INSPECTION

3.1 Findings

a. General. The on-site inspection of Wolf Creek Dam consisted of:

1. Visual inspection of the embankment, abutments, and embankment toe.
2. Visual examination of the emergency spillway and exposed portions of the primary spillway.
3. Observations of factors affecting the runoff potential of the drainage basin.
4. Evaluation of downstream hazard potential.

The specific observations are illustrated in Plate 7 and in the photographs in Appendix C.

b. Embankment. The general inspection of the embankment consisted of searching for indications of structural distress, such as cracks, subsidence, bulging, wet areas, seeps and boils, and observing general maintenance conditions, vegetative cover, erosion, and other surficial features.

In general, the condition of the dam is considered to be good. However, numerous wet areas were found along the downstream slope and toe areas of the dam. Except for one seepage point located near the right abutment, no measurable seepage was found to be associated with these wet areas. In their present extent and condition, these wet areas are not considered to be a threat to the overall stability of the embankment at this time. However, periodic inspection would be required to insure that the conditions are not changing.

The top of the embankment was surveyed relative to the pool level on the date of inspection, which was estimated to be at Elevation 1662.6, the spillway crest level (Elevation 1664.5), and the crest of the embankment was found to be approximately 0.7 to 1.0 foot above the design elevation of 1670. The dam crest profile is illustrated on Plate 8.

c. Appurtenant Structures. The appurtenant structures were examined for deterioration and other signs of distress and obstructions that would limit flow. In general, the structures were found to be in good condition. No deficiencies were noted at this time.



d. Reservoir Area. A map review indicates that the watershed is predominantly covered with woodlands. A small portion of the watershed has been strip mined. A review of the regional geology (Appendix E) indicates that the reservoir slopes are not likely to be susceptible to massive landslides which would affect the storage volume of the reservoir.

e. Downstream Channel. Below the dam, Wolf Run flows through an uninhabited valley before flowing under U.S. Route 219 approximately 3-1/2 miles downstream from the dam. Further description of the downstream conditions is included in Section 1.2b.

3.2 Evaluation. The condition of the dam is considered to be good. The present extent of the wet areas on the downstream face and along the toe of the dam does not appear to be affecting the stability of the embankment at this time. However, continued inspection of these areas is required to determine if the extent of the wet areas is increasing or seepage and sloughing conditions are developing.

## SECTION 4 OPERATIONAL FEATURES

4.1 Procedure. There are no formal operating procedures for the dam. The reservoir is normally maintained at the crest level of the primary spillways for this dam and Galion Bay Dam with excess inflow discharging over the uncontrolled primary or emergency spillway.

4.2 Maintenance of the Dam. The maintenance of the dam is considered to be fair. The downstream face of the dam is covered with partially established grass which appears to be mowed occasionally. Some small trees under 5 feet high were found to be growing on the upstream face.

4.3 Maintenance of Operating Facilities. The only operational feature of the dam is the reservoir outlet pipe sluice gate operated by a hoist located at the drop inlet structure. The reservoir outlet sluice gate was operated and was observed to be functional.

4.4 Warning System. No formal warning system exists for the dam. Telephone communication facilities are available via residences in the vicinity of the dam.

4.5 Evaluation. While the maintenance condition of the dam is considered to be fair, the maintenance condition of the operating facilities is assessed to be good. The embankment should be periodically inspected with emphasis on the wet areas on the downstream face and along the toe of the dam to determine that the conditions are not changing.

SECTION 5  
HYDRAULICS AND HYDROLOGY

5.1 Evaluation of Features

a. Design Data. Wolf Creek Dam is one of three dams which impound Lake Rene. Lake Rene has a watershed of 4.4 square miles and a lake area of 310 acres at normal pool elevation. The flood discharge facilities for Lake Rene consist of the primary and emergency spillways of Galion Bay and Wolf Creek dams. The combined capacity of the spillways of Galion Bay and Wolf Creek dams was determined to be 5300 cfs with no freeboard.

b. Experience Data. As previously stated, Wolf Creek Dam is classified as an intermediate dam in the high hazard category. Under the recommended criteria for evaluating emergency spillway discharge capacity, such impoundments are required to pass full PMF.

The PMF inflow hydrograph for the reservoir was determined using the Dam Safety Version of the HEC-1 computer program developed by the Hydrologic Engineering Center of the U.S. Army, Corps of Engineers. Data used for the computer analysis are presented in Appendix D. The PMF inflow hydrograph was found to have a peak flow of 10,851 cfs. The computer input and summary of computer output are also included in Appendix D.

c. Visual Observations. On the date of inspection, no conditions were observed that would indicate that the capacity of the spillways of Galion Bay and Wolf Creek dams would be significantly reduced in the event of a flood.

d. Overtopping Potential. Various percentages of PMF inflow hydrograph were routed through the reservoir. It was found that the spillways of Galion Bay and Wolf Creek dams can pass 90 percent PMF without overtopping the embankment. For 100 percent PMF, a low spot on the crest of Galion Bay Dam, which was found to be 0.1 foot above the design elevation of 1670, would be overtopped for a duration of two hours with a maximum depth of 0.2 foot. It is estimated that overtopping of the dam by a maximum of 0.2 foot would not constitute a significant potential for embankment breaching.

e. Spillway Adequacy. Since the flood discharge facilities of Lake Rene cannot pass the recommended spillway design of 100 percent PMF without overtopping the embankment, the spillway capacity is rated to be inadequate.



## SECTION 6 STRUCTURAL STABILITY

### 6.1 Evaluation of Structural Stability

#### a. Visual Observations

(1) Embankment. As discussed in Section 3, the field observations did not reveal any signs of distress that would significantly affect the stability of the dam at this time. However, in view of the wet areas observed on the downstream slope, concern exists as to the ability of the toe trench drain to lower the phreatic surface through the embankment. Periodic inspection of the wet areas is recommended. Remedial measures should be taken if the extent of the wet areas increases or seepage or sloughing conditions develop.

(2) Appurtenant Structures. The performance of the appurtenant structures is considered to be satisfactory.

#### b. Design and Construction Data

(1) Embankment. Available information indicates that the stability of the embankment was analyzed for steady-state seepage and rapid draw-down conditions based on assumed soil strength parameters. The factor of safety was reported to be 2.1 under steady-state seepage stability of the downstream slope and 1.2 for the rapid drawdown condition of the upstream slope. Assumed strength parameters for internal friction angle, 25 degrees, and cohesion, 200 psf, appear to be in a reasonable range relative to the indicated classification of embankment material, silty clays with low plasticity.

(2) Appurtenant Structures. Review of the design drawings indicates that there are no apparent structural deficiencies that would significantly affect the performance of the appurtenant structures.

c. Operating Records. There are no operating records kept for the dam.

d. Post-Construction Changes. None reported.

e. Seismic Stability. The dam is located in Seismic Zone 1, and based on visual observations the static stability of the dam is considered to be adequate. Therefore, based on the recommended criteria for evaluation of seismic stability of dams, the structures are presumed to present no hazard from earthquakes.

SECTION 7  
ASSESSMENT AND RECOMMENDATIONS/PROPOSED REMEDIAL MEASURES

7.1 Dam Assessment

a. Assessment. The visual observations indicate that Wolf Creek Dam is in good condition. The swampy areas observed on the downstream slope and in the area below the toe of the dam are not considered to be serious relative to the overall performance of the dam at this time. However, these areas should be periodically observed to determine if the conditions are changing.

The flood discharge capacity of Lake Rene via the spillways of Galion Bay and Wolf Creek dams was found to be 90 percent PMF and is therefore classified to be inadequate according to the recommended criteria.

b. Adequacy of Information. Available information in conjunction with visual observations and the previous experience of the inspectors are considered to be sufficient to make a reasonable assessment of the condition of the dam.

c. Urgency. The following recommendations should be implemented as soon as possible or on a continuing basis.

d. Necessity for Additional Data. No additional data are considered required at this time.


7.2 Recommendations/Remedial Measures. It is recommended that:

1. The wet areas located along the downstream face and the toe of the embankment should be periodically observed. Necessary remedial work should be performed if the extent of the wet areas increases or seepage and sloughing conditions develop.
2. Around-the-clock surveillance should be provided during unusually heavy runoff and a formal warning system should be developed to alert the downstream residents in the event of emergencies.
3. Small trees on the upstream face of the dam should be removed.
4. The dam and appurtenant structures should be inspected regularly and necessary maintenance should be performed.



**PLATES**



DRAWN BY ACS CHECKED BY BE 6-4-79 DRAWING NUMBER 78-367-B137  
 4-24-79 APPROVED BY JPD 6-4-79







D'APPOLONIA

DRAWN BY

[illegible]






PLATE 2

**D'APPOLONIA**

DRAWN BY	ACS	CHECKED BY	6-4-79	DRAWING NUMBER
	5-22-79	APPROVED BY	6-4-79	

78-367-B139







PLATE 3

**D'APPOLONIA**



DRAWN BY	ACS	CHECKED BY	BB	DRAWING NUMBER	6-4-77	78-367-B   40
					6-4-77	







PLATE 4

**D'APPOLONIA**




DRAWN BY	ACS	CHECKED BY	6-4-77	DRAWING	78-367-B141
	5-22-79	APPROVED BY	6-4-77	NUMBER	



PROFILE EMERGENCY SPILLWAY-WOLF CREEK DAM

SCALE 1" = 50' Horiz  
1" = 10' Vert



WOLF CREEK CROSS SECTIONS

SCALE 1" = 50'

17-108-5  
 DEPARTMENT OF THE WATER & POWER  
 RESOURCES DIVISION  
 WATERS ON *Wolf Creek* A.D. 19  
*John R. Sales*

1011100  
*C. L. Currell*  
 S. B. Currell  
 S. B. Currell






*John Robert Sales*  
 JOHN ROBERT SALES P.E.

PROFILE & CROSS SECTIONS  
 PROPOSED  
 WOLF CREEK DAM  
 MADE FOR  
 TREASURE LAKE, INC.  
 R.M. KEDDAL AND ASSOCIATES INC.  
 Engineers, Planners and Surveyors  
 3400 SOUTH PARK ROAD  
 BETHEL PARK, PA.  
 DATE AUG. 1968  
 JOB NO. 137  
 SCALE: AS SHOWN




PLATE 5

**D'APPOLONIA**

DRAWN BY ACS CHECKED BY BE 5-22-79 APPROVED BY JWP 5-22-79 DRAWING NUMBER 78-367-B142




1/4" x 6" Steel Plate  
Continuous Thru Constr. Joint  
Splices Shall Be Either:  
1. Bolted  
2. Lapped 3" And Bolted  
3. Lapped 3" And Fillet Welded




**CONSTRUCTION DETAILS**  
 Portland cement Type C10-54, C150-56 or C175-56 Air Entraining shall be used.  
 2. All Reinforcing Steel placed in Concrete placed against the ground shall have a minimum of 3" clear cover. All Reinforcing Steel placed in Concrete placed in forms shall have a minimum of 2" clear cover.  
 3. All exposed edges of concrete to have 3/4" chamfer unless otherwise noted.  
 4. Bar dimensions go out to cut of bar.  
 5. Radius of bends:  
 3 bar diam for sizes 6, No. 7  
 4 bar diam for sizes 8, No. 9  
 5 bar diam for sizes 10, No. 11  
 6 bar diam for sizes 12, No. 14  
 8 bar diam for sizes 16, No. 18  
 10 bar diam for sizes 20, No. 22  
 12 bar diam for sizes 24, No. 28  
 14 bar diam for sizes 30, No. 36  
 16 bar diam for sizes 36, No. 42  
 18 bar diam for sizes 42, No. 48  
 20 bar diam for sizes 48, No. 54  
 24 bar diam for sizes 60, No. 66  
 28 bar diam for sizes 72, No. 78  
 32 bar diam for sizes 84, No. 90  
 36 bar diam for sizes 96, No. 102  
 40 bar diam for sizes 108, No. 114  
 44 bar diam for sizes 120, No. 126  
 48 bar diam for sizes 132, No. 138  
 52 bar diam for sizes 144, No. 150  
 56 bar diam for sizes 156, No. 162  
 60 bar diam for sizes 168, No. 174  
 64 bar diam for sizes 180, No. 186  
 68 bar diam for sizes 192, No. 198  
 72 bar diam for sizes 204, No. 210  
 76 bar diam for sizes 216, No. 222  
 80 bar diam for sizes 228, No. 234  
 84 bar diam for sizes 240, No. 246  
 88 bar diam for sizes 252, No. 258  
 92 bar diam for sizes 264, No. 270  
 96 bar diam for sizes 276, No. 282  
 100 bar diam for sizes 288, No. 294  
 104 bar diam for sizes 300, No. 306  
 108 bar diam for sizes 312, No. 318  
 112 bar diam for sizes 324, No. 330  
 116 bar diam for sizes 336, No. 342  
 120 bar diam for sizes 348, No. 354  
 124 bar diam for sizes 360, No. 366  
 128 bar diam for sizes 372, No. 378  
 132 bar diam for sizes 384, No. 390  
 136 bar diam for sizes 396, No. 402  
 140 bar diam for sizes 408, No. 414  
 144 bar diam for sizes 420, No. 426  
 148 bar diam for sizes 432, No. 438  
 152 bar diam for sizes 444, No. 450  
 156 bar diam for sizes 456, No. 462  
 160 bar diam for sizes 468, No. 474  
 164 bar diam for sizes 480, No. 486  
 168 bar diam for sizes 492, No. 498  
 172 bar diam for sizes 504, No. 510  
 176 bar diam for sizes 516, No. 522  
 180 bar diam for sizes 528, No. 534  
 184 bar diam for sizes 540, No. 546  
 188 bar diam for sizes 552, No. 558  
 192 bar diam for sizes 564, No. 570  
 196 bar diam for sizes 576, No. 582  
 200 bar diam for sizes 588, No. 594  
 204 bar diam for sizes 600, No. 606  
 208 bar diam for sizes 612, No. 618  
 212 bar diam for sizes 624, No. 630  
 216 bar diam for sizes 636, No. 642  
 220 bar diam for sizes 648, No. 654  
 224 bar diam for sizes 660, No. 666  
 228 bar diam for sizes 672, No. 678  
 232 bar diam for sizes 684, No. 690  
 236 bar diam for sizes 696, No. 702  
 240 bar diam for sizes 708, No. 714  
 244 bar diam for sizes 720, No. 726  
 248 bar diam for sizes 732, No. 738  
 252 bar diam for sizes 744, No. 750  
 256 bar diam for sizes 756, No. 762  
 260 bar diam for sizes 768, No. 774  
 264 bar diam for sizes 780, No. 786  
 268 bar diam for sizes 792, No. 798  
 272 bar diam for sizes 804, No. 810  
 276 bar diam for sizes 816, No. 822  
 280 bar diam for sizes 828, No. 834  
 284 bar diam for sizes 840, No. 846  
 288 bar diam for sizes 852, No. 858  
 292 bar diam for sizes 864, No. 870  
 296 bar diam for sizes 876, No. 882  
 300 bar diam for sizes 888, No. 894  
 304 bar diam for sizes 900, No. 906  
 308 bar diam for sizes 912, No. 918  
 312 bar diam for sizes 924, No. 930  
 316 bar diam for sizes 936, No. 942  
 320 bar diam for sizes 948, No. 954  
 324 bar diam for sizes 960, No. 966  
 328 bar diam for sizes 972, No. 978  
 332 bar diam for sizes 984, No. 990  
 336 bar diam for sizes 996, No. 1002  
 340 bar diam for sizes 1008, No. 1014  
 344 bar diam for sizes 1020, No. 1026  
 348 bar diam for sizes 1032, No. 1038  
 352 bar diam for sizes 1044, No. 1050  
 356 bar diam for sizes 1056, No. 1062  
 360 bar diam for sizes 1068, No. 1074  
 364 bar diam for sizes 1080, No. 1086  
 368 bar diam for sizes 1092, No. 1098  
 372 bar diam for sizes 1104, No. 1110  
 376 bar diam for sizes 1116, No. 1122  
 380 bar diam for sizes 1128, No. 1134  
 384 bar diam for sizes 1140, No. 1146  
 388 bar diam for sizes 1152, No. 1158  
 392 bar diam for sizes 1164, No. 1170  
 396 bar diam for sizes 1176, No. 1182  
 400 bar diam for sizes 1188, No. 1194  
 404 bar diam for sizes 1200, No. 1206  
 408 bar diam for sizes 1212, No. 1218  
 412 bar diam for sizes 1224, No. 1230  
 416 bar diam for sizes 1236, No. 1242  
 420 bar diam for sizes 1248, No. 1254  
 424 bar diam for sizes 1260, No. 1266  
 428 bar diam for sizes 1272, No. 1278  
 432 bar diam for sizes 1284, No. 1290  
 436 bar diam for sizes 1296, No. 1302  
 440 bar diam for sizes 1308, No. 1314  
 444 bar diam for sizes 1320, No. 1326  
 448 bar diam for sizes 1332, No. 1338  
 452 bar diam for sizes 1344, No. 1350  
 456 bar diam for sizes 1356, No. 1362  
 460 bar diam for sizes 1368, No. 1374  
 464 bar diam for sizes 1380, No. 1386  
 468 bar diam for sizes 1392, No. 1398  
 472 bar diam for sizes 1404, No. 1410  
 476 bar diam for sizes 1416, No. 1422  
 480 bar diam for sizes 1428, No. 1434  
 484 bar diam for sizes 1440, No. 1446  
 488 bar diam for sizes 1452, No. 1458  
 492 bar diam for sizes 1464, No. 1470  
 496 bar diam for sizes 1476, No. 1482  
 500 bar diam for sizes 1488, No. 1494  
 504 bar diam for sizes 1500, No. 1506  
 508 bar diam for sizes 1512, No. 1518  
 512 bar diam for sizes 1524, No. 1530  
 516 bar diam for sizes 1536, No. 1542  
 520 bar diam for sizes 1548, No. 1554  
 524 bar diam for sizes 1560, No. 1566  
 528 bar diam for sizes 1572, No. 1578  
 532 bar diam for sizes 1584, No. 1590  
 536 bar diam for sizes 1596, No. 1602  
 540 bar diam for sizes 1608, No. 1614  
 544 bar diam for sizes 1620, No. 1626  
 548 bar diam for sizes 1632, No. 1638  
 552 bar diam for sizes 1644, No. 1650  
 556 bar diam for sizes 1656, No. 1662  
 560 bar diam for sizes 1668, No. 1674  
 564 bar diam for sizes 1680, No. 1686  
 568 bar diam for sizes 1692, No. 1698  
 572 bar diam for sizes 1704, No. 1710  
 576 bar diam for sizes 1716, No. 1722  
 580 bar diam for sizes 1728, No. 1734  
 584 bar diam for sizes 1740, No. 1746  
 588 bar diam for sizes 1752, No. 1758  
 592 bar diam for sizes 1764, No. 1770  
 596 bar diam for sizes 1776, No. 1782  
 600 bar diam for sizes 1788, No. 1794  
 604 bar diam for sizes 1800, No. 1806  
 608 bar diam for sizes 1812, No. 1818  
 612 bar diam for sizes 1824, No. 1830  
 616 bar diam for sizes 1836, No. 1842  
 620 bar diam for sizes 1848, No. 1854  
 624 bar diam for sizes 1860, No. 1866  
 628 bar diam for sizes 1872, No. 1878  
 632 bar diam for sizes 1884, No. 1890  
 636 bar diam for sizes 1896, No. 1902  
 640 bar diam for sizes 1908, No. 1914  
 644 bar diam for sizes 1920, No. 1926  
 648 bar diam for sizes 1932, No. 1938  
 652 bar diam for sizes 1944, No. 1950  
 656 bar diam for sizes 1956, No. 1962  
 660 bar diam for sizes 1968, No. 1974  
 664 bar diam for sizes 1980, No. 1986  
 668 bar diam for sizes 1992, No. 1998  
 672 bar diam for sizes 2004, No. 2010  
 676 bar diam for sizes 2016, No. 2022  
 680 bar diam for sizes 2028, No. 2034  
 684 bar diam for sizes 2040, No. 2046  
 688 bar diam for sizes 2052, No. 2058  
 692 bar diam for sizes 2064, No. 2070  
 696 bar diam for sizes 2076, No. 2082  
 700 bar diam for sizes 2088, No. 2094  
 704 bar diam for sizes 2100, No. 2106  
 708 bar diam for sizes 2112, No. 2118  
 712 bar diam for sizes 2124, No. 2130  
 716 bar diam for sizes 2136, No. 2142  
 720 bar diam for sizes 2148, No. 2154  
 724 bar diam for sizes 2160, No. 2166  
 728 bar diam for sizes 2172, No. 2178  
 732 bar diam for sizes 2184, No. 2190  
 736 bar diam for sizes 2196, No. 2202  
 740 bar diam for sizes 2208, No. 2214  
 744 bar diam for sizes 2220, No. 2226  
 748 bar diam for sizes 2232, No. 2238  
 752 bar diam for sizes 2244, No. 2250  
 756 bar diam for sizes 2256, No. 2262  
 760 bar diam for sizes 2268, No. 2274  
 764 bar diam for sizes 2280, No. 2286  
 768 bar diam for sizes 2292, No. 2298  
 772 bar diam for sizes 2304, No. 2310  
 776 bar diam for sizes 2316, No. 2322  
 780 bar diam for sizes 2328, No. 2334  
 784 bar diam for sizes 2340, No. 2346  
 788 bar diam for sizes 2352, No. 2358  
 792 bar diam for sizes 2364, No. 2370  
 796 bar diam for sizes 2376, No. 2382  
 800 bar diam for sizes 2388, No. 2394  
 804 bar diam for sizes 2400, No. 2406  
 808 bar diam for sizes 2412, No. 2418  
 812 bar diam for sizes 2424, No. 2430  
 816 bar diam for sizes 2436, No. 2442  
 820 bar diam for sizes 2448, No. 2454  
 824 bar diam for sizes 2460, No. 2466  
 828 bar diam for sizes 2472, No. 2478  
 832 bar diam for sizes 2484, No. 2490  
 836 bar diam for sizes 2496, No. 2502  
 840 bar diam for sizes 2508, No. 2514  
 844 bar diam for sizes 2520, No. 2526  
 848 bar diam for sizes 2532, No. 2538  
 852 bar diam for sizes 2544, No. 2550  
 856 bar diam for sizes 2556, No. 2562  
 860 bar diam for sizes 2568, No. 2574  
 864 bar diam for sizes 2580, No. 2586  
 868 bar diam for sizes 2592, No. 2598  
 872 bar diam for sizes 2604, No. 2610  
 876 bar diam for sizes 2616, No. 2622  
 880 bar diam for sizes 2628, No. 2634  
 884 bar diam for sizes 2640, No. 2646  
 888 bar diam for sizes 2652, No. 2658  
 892 bar diam for sizes 2664, No. 2670  
 896 bar diam for sizes 2676, No. 2682  
 900 bar diam for sizes 2688, No. 2694  
 904 bar diam for sizes 2700, No. 2706  
 908 bar diam for sizes 2712, No. 2718  
 912 bar diam for sizes 2724, No. 2730  
 916 bar diam for sizes 2736, No. 2742  
 920 bar diam for sizes 2748, No. 2754  
 924 bar diam for sizes 2760, No. 2766  
 928 bar diam for sizes 2772, No. 2778  
 932 bar diam for sizes 2784, No. 2790  
 936 bar diam for sizes 2796, No. 2802  
 940 bar diam for sizes 2808, No. 2814  
 944 bar diam for sizes 2820, No. 2826  
 948 bar diam for sizes 2832, No. 2838  
 952 bar diam for sizes 2844, No. 2850  
 956 bar diam for sizes 2856, No. 2862  
 960 bar diam for sizes 2868, No. 2874  
 964 bar diam for sizes 2880, No. 2886  
 968 bar diam for sizes 2892, No. 2898  
 972 bar diam for sizes 2904, No. 2910  
 976 bar diam for sizes 2916, No. 2922  
 980 bar diam for sizes 2928, No. 2934  
 984 bar diam for sizes 2940, No. 2946  
 988 bar diam for sizes 2952, No. 2958  
 992 bar diam for sizes 2964, No. 2970  
 996 bar diam for sizes 2976, No. 2982  
 1000 bar diam for sizes 2988, No. 2994  
 1004 bar diam for sizes 3000, No. 3006  
 1008 bar diam for sizes 3012, No. 3018  
 1012 bar diam for sizes 3024, No. 3030  
 1016 bar diam for sizes 3036, No. 3042  
 1020 bar diam for sizes 3048, No. 3054  
 1024 bar diam for sizes 3060, No. 3066  
 1028 bar diam for sizes 3072, No. 3078  
 1032 bar diam for sizes 3084, No. 3090  
 1036 bar diam for sizes 3096, No. 3102  
 1040 bar diam for sizes 3108, No. 3114  
 1044 bar diam for sizes 3120, No. 3126  
 1048 bar diam for sizes 3132, No. 3138  
 1052 bar diam for sizes 3144, No. 3150  
 1056 bar diam for sizes 3156, No. 3162  
 1060 bar diam for sizes 3168, No. 3174  
 1064 bar diam for sizes 3180, No. 3186  
 1068 bar diam for sizes 3192, No. 3198  
 1072 bar diam for sizes 3204, No. 3210  
 1076 bar diam for sizes 3216, No. 3222  
 1080 bar diam for sizes 3228, No. 3234  
 1084 bar diam for sizes 3240, No. 3246  
 1088 bar diam for sizes 3252, No. 3258  
 1092 bar diam for sizes 3264, No. 3270  
 1096 bar diam for sizes 3276, No. 3282  
 1100 bar diam for sizes 3288, No. 3294  
 1104 bar diam for sizes 3300, No. 3306  
 1108 bar diam for sizes 3312, No. 3318  
 1112 bar diam for sizes 3324, No. 3330  
 1116 bar diam for sizes 3336, No. 3342  
 1120 bar diam for sizes 3348, No. 3354  
 1124 bar diam for sizes 3360, No. 3366  
 1128 bar diam for sizes 3372, No. 3378  
 1132 bar diam for sizes 3384, No. 3390  
 1136 bar diam for sizes 3396, No. 3402  
 1140 bar diam for sizes 3408, No. 3414  
 1144 bar diam for sizes 3420, No. 3426  
 1148 bar diam for sizes 3432, No. 3438  
 1152 bar diam for sizes 3444, No. 3450  
 1156 bar diam for sizes 3456, No. 3462  
 1160 bar diam for sizes 3468, No. 3474  
 1164 bar diam for sizes 3480, No. 3486  
 1168 bar diam for sizes 3492, No. 3498  
 1172 bar diam for sizes 3504, No. 3510  
 1176 bar diam for sizes 3516, No. 3522  
 1180 bar diam for sizes 3528, No. 3534  
 1184 bar diam for sizes 3540, No. 3546  
 1188 bar diam for sizes 3552, No. 3558  
 1192 bar diam for sizes 3564, No. 3570  
 1196 bar diam for sizes 3576, No. 3582  
 1200 bar diam for sizes 3588, No. 3594  
 1204 bar diam for sizes 3600, No. 3606  
 1208 bar diam for sizes 3612, No. 3618  
 1212 bar diam for sizes 3624, No. 3630  
 1216 bar diam for sizes 3636, No. 3642  
 1220 bar diam for sizes 3648, No. 3654  
 1224 bar diam for sizes 3660, No. 3666  
 1228 bar diam for sizes 3672, No. 3678  
 1232 bar diam for sizes 3684, No. 3690  
 1236 bar diam for sizes 3696, No. 3702  
 1240 bar diam for sizes 3708, No. 3714  
 1244 bar diam for sizes 3720, No. 3726  
 1248 bar diam for sizes 3732, No. 3738  
 1252 bar diam for sizes 3744, No. 3750  
 1256 bar diam for sizes 3756, No. 3762  
 1260 bar diam for sizes 3768, No. 3774  
 1264 bar diam for sizes 3780, No. 3786  
 1268 bar diam for sizes 3792, No. 3798  
 1272 bar diam for sizes 3804, No. 3810  
 1276 bar diam for sizes 3816, No. 3822  
 1280 bar diam for sizes 3828, No. 3834  
 1284 bar diam for sizes 3840, No. 3846  
 1288 bar diam for sizes 3852, No. 3858  
 1292 bar diam for sizes 3864, No. 3870  
 1296 bar diam for sizes 3876, No. 3882  
 1300 bar diam for sizes 3888, No. 3894  
 1304 bar diam for sizes 3900, No. 3906  
 1308 bar diam for sizes 3912, No. 3918  
 1312 bar diam for sizes 3924, No. 3930  
 1316 bar diam for sizes 3936, No. 3942  
 1320 bar diam for sizes 3948, No. 3954  
 1324 bar diam for sizes 3960, No. 3966  
 1328 bar diam for sizes 3972, No. 3978  
 1332 bar diam for sizes 3984, No. 3990  
 1336 bar diam for sizes 3996, No. 4002  
 1340 bar diam for sizes 4008, No. 4014  
 1344 bar diam for sizes 4020, No. 4026  
 1348 bar diam for sizes 4032, No. 4038  
 1352 bar diam for sizes 4044, No. 4050  
 1356 bar diam for sizes 4056, No. 4062  
 1360 bar diam for sizes 4068, No. 4074  
 1364 bar diam for sizes 4080, No. 4086  
 1368 bar diam for sizes 4092, No. 4098  
 1372 bar diam for sizes 4104, No. 4110  
 1376 bar diam for sizes 4116, No. 4122  
 1380 bar diam for sizes 4128, No. 4134  
 1384 bar diam for sizes 4140, No. 4146  
 1388 bar diam for sizes 4152, No. 4158  
 1392 bar diam for sizes 4164, No. 4170  
 1396 bar diam for sizes 4176, No. 4182  
 1400 bar diam for sizes 4188, No. 4194  
 1404 bar diam for sizes 4200, No. 4206  
 1408 bar diam for sizes 4212, No. 4218  
 1412 bar diam for sizes 4224, No. 4230  
 1416 bar diam for sizes 4236, No. 4242  
 1420 bar diam for sizes 4248, No. 4254  
 1424 bar diam for sizes 4260, No. 4266  
 1428 bar diam for sizes 4272, No. 4278  
 1432 bar diam for sizes 4284, No. 4290  
 1436 bar diam for sizes 4296, No. 4302  
 1440 bar diam for sizes 4308, No. 4314  
 1444 bar diam for sizes 4320, No. 4326  
 1448 bar diam for sizes 4332, No. 4338  
 1452 bar diam for sizes 4344, No. 4350  
 1456 bar diam for sizes 4356, No. 4362  
 1460 bar diam for sizes 4368, No. 4374  
 1464 bar diam for sizes 4380, No. 4386  
 1468 bar diam for sizes 4392, No. 4398  
 1472 bar diam for sizes 4404, No. 4410  
 1476 bar diam for sizes 4416, No. 4422  
 1480 bar diam for sizes 4428, No. 4434  
 1484 bar diam for sizes 4440, No. 4446  
 1488 bar diam for sizes 4452, No. 4458  
 1492 bar diam for sizes 4464, No. 4470  
 1496 bar diam for sizes 4476, No. 4482  
 1500 bar diam for sizes 4488, No. 4494  
 1504 bar diam for sizes 4500, No. 4506  
 1508 bar diam for sizes 4512, No. 4518  
 1512 bar diam for sizes 4524, No. 4530  
 1516 bar diam for sizes 4536, No. 4542  
 1520 bar diam for sizes 4548, No. 4554  
 1524 bar diam for sizes 4560, No. 4566  
 1528 bar diam for sizes 4572, No. 4578  
 1532 bar diam for sizes 4584, No. 4590  
 1536 bar diam for sizes 4596, No. 4602  
 1540 bar diam for sizes 4608, No. 4614  
 1544 bar diam for sizes 4620, No. 4626  
 1548 bar diam for sizes 4632, No. 4638  
 1552 bar diam for sizes 4644, No. 4650  
 1556 bar diam for sizes 4656, No. 4662  
 1560 bar diam for sizes 4668, No. 4674  
 1564 bar diam for sizes 4680, No. 4686  
 1568 bar diam for sizes 4692, No. 4698  
 1572 bar diam for sizes 4704, No. 4710  
 1576 bar diam for sizes 4716, No. 4722  
 1580 bar diam for sizes 4728, No. 4734  
 1584 bar diam for sizes 4740, No. 4746  
 1588 bar diam for sizes 4752, No. 4758  
 1592 bar diam for sizes 4764, No. 4770  
 1596 bar diam for sizes 4776, No. 4782  
 1600 bar diam for sizes 4788, No. 4794  
 1604 bar diam for sizes 4800, No. 4806  
 1608 bar diam for sizes 4812, No. 4818  
 1612 bar diam for sizes 4824, No. 4830  
 1616 bar diam for sizes 4836, No. 4842  
 1620 bar diam for sizes 4848, No. 4854  
 1624 bar diam for sizes 4860, No. 4866  
 1628 bar diam for sizes 4872, No. 4878  
 1632 bar diam for sizes 4884, No. 4890  
 1636 bar diam for sizes 4896, No. 4902  
 1640 bar diam for sizes 4908, No. 4914  
 1644 bar diam for sizes 4920, No. 4926  
 1648 bar diam for sizes 4932, No. 4938  
 1652 bar diam for sizes 4944, No. 4950  
 1656 bar diam for sizes 4956, No. 4962  
 1660 bar diam for sizes 4968, No. 4974  
 1664 bar diam for sizes 4980, No. 4986  
 1668 bar diam for sizes 4992, No. 4998  
 1672 bar diam for sizes 5004, No. 5010  
 1676 bar diam for sizes 5016, No. 5022  
 1680 bar diam for sizes 5028, No. 5034  
 1684 bar diam for sizes 5040, No. 5046  
 1688 bar diam for sizes 5052, No. 5058  
 1692 bar diam for sizes 5064, No. 5070  
 1696 bar diam for sizes 5076, No. 5082  
 1700 bar diam for sizes 5088, No. 5094  
 1704 bar diam for sizes 5100, No. 5106  
 1708 bar diam for sizes 5112, No. 5118  
 1712 bar diam for sizes 5124, No. 5130  
 1716 bar diam for sizes 5136, No. 5142  
 1720 bar diam for sizes 5148, No. 5154  
 1724 bar diam for sizes 5160, No. 5166  
 1728 bar diam for sizes 5172, No. 5178  
 1732 bar diam for sizes 5184, No. 5190  
 1736 bar diam for sizes 5196, No. 5202  
 1740 bar diam for sizes 5208, No. 5214  
 1744 bar diam for sizes 5220, No. 5226  
 1748 bar diam for sizes 5232, No. 5238  
 1752 bar diam for sizes 5244, No. 5250  
 1756 bar diam for sizes 5256, No. 5262  
 1760 bar diam for sizes 5268, No. 5274  
 1764 bar diam for sizes 5280, No. 5286  
 1768 bar diam for sizes 5292, No. 5298  
 1772 bar diam for sizes 5304, No. 5310  
 1776 bar diam for sizes 5316, No. 5322  
 1780 bar diam for sizes 5328, No. 5334  
 1784 bar diam for sizes 5340, No. 5346  
 1788 bar diam for sizes 5352, No. 5358  
 1792 bar diam for sizes 5364, No. 5370  
 1796 bar diam for sizes 5376, No. 5382  
 1800 bar diam for sizes 5388, No. 5394  
 1804 bar diam for sizes 5400, No. 5406  
 1808 bar diam for sizes 5412, No. 5418  
 1812 bar diam for sizes 5424, No. 5






**WALL ASSEMBLY**  
 shall be Gray Iron Casting  
 shall consist of a 1" Dia  
 8" from the outside  
 1/2" dia  
 shall consist of a hook  
 1/2" dia underside and a  
 1/2" dia bolt at the



STEEL SCHEDULE																			
MARK	SIZE	QUANTITY	LENGTH	TYPE	B	C	TOTAL LENGTH	MARK	SIZE	QUANTITY	LENGTH	TYPE	B	C	TOTAL LENGTH				
B1	6	17	7-10	1	---	---	133-08												
B2	6	6	7-10	1	---	---	100-0												
B3	6	26	5-9	21	2-7	5-2	332-6												
B4	6	6	5-6	1	---	---	100-0												
B5	6	12	7-10	1	---	---	50-0												
B6	6	2	3-0	1	---	---	5-0												
B7	6	4	3-1	21	1-0	5-1	26-4												
B8	6	2	5-1	21	1-0	5-1	12-2												
B9	6	16	5-1	21	1-0	5-1	97-4												
B10	6	2	5-1	21	1-0	5-1	12-2												
B11	6	2	4-6	1	---	---	7-4												
B12	6	4	3-2	1	---	---	12-0												
B13	6	14	7-6	21	3-0	7-6	147-0												
B14	6	4	7-11	21	0-3	7-6	31-8												
B15	6	4	1-9	21	0-3	7-6	31-0												
B16	6	2	5-7	21	1-1	7-6	17-2												
B17	6	2	2-3	1	---	---	5-8												
B18	6	2	2-3	1	---	---	5-8												
B19	6	6	2-0	1	---	---	12-0												

DRAWN BY ACS  
 CHECKED BY 6-4-79  
 APPROVED BY 6-4-79  
 DRAWING NUMBER 57-A30




**NOTES:**

1. POOL LEVEL DATE OF INSPECTION 0.2 FT. ABOVE PRIMARY SPILLWAY CREST
2. EMERGENCY SPILLWAY FREEBOARD = 7.6 FT.

WOLF CREEK DAM  
 GENERAL PLAN  
 FIELD INSPECTION NOTES  
 FIELD INSPECTION DATE: APR. 4, 79

**D'APPOLONIA**

DRAWN BY	ACS	CHECKED BY	6E	6/26/77	DRAWING NUMBER	367-A43
	6-28-79	APPROVED BY	380	7-3-79		



# **DAM CREST PROFILE** (LOOKING DOWNSTREAM)

NOTE:  
DAM CREST IS SURVEYED RELATIVE  
TO PRIMARY SPILLWAY CREST LEVEL.

PLATE 8

WOLF CREEK DAM  
DAM CREST SURVEY  
FIELD INSPECTION DATE: APR. 4, 79

**D'APPOLONIA**



**APPENDIX A**  
**CHECKLIST**  
**VISUAL INSPECTION**  
**PHASE I**

# APPENDIX A

## CHECKLIST VISUAL INSPECTION PHASE I

NAME OF DAM Wolf Creek Dam COUNTY Clearfield STATE Pennsylvania ID# NDI I.D. PA-748  
 TYPE OF DAM Earth HAZARD CATEGORY High DER I.D. 17-108

DATE(S) INSPECTION April 4, 1979 WEATHER Partly Cloudy TEMPERATURE 40s

POOL ELEVATION AT TIME OF INSPECTION 1662.5 M.S.L. TAILWATER AT TIME OF INSPECTION 1636± M.S.L.

### INSPECTION PERSONNEL:

Bilgin Erel  
Wah-Tak Chan  
 \_\_\_\_\_

### REVIEW INSPECTION PERSONNEL:

(May 4, 1979)

E. D'Appolonia  
L. D. Andersen  
J. H. Poellot

Bilgin Erel

Bilgin Erel RECORDER

**VISUAL INSPECTION  
PHASE I  
EMBANKMENT**

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
SURFACE CRACKS	None.	
UNUSUAL MOVEMENT OR CRACKING AT OR BEYOND THE TOE	None.	
SLOUGHING OR EROSION OF EMBANKMENT AND ABUTMENT SLOPES	None significant.	
VERTICAL AND HORIZONTAL ALIGNMENT OF THE CREST	Crest of the dam is about 0.7 to 1.0 foot above the design crest level of Elevation 1670.	
RIPRAP FAILURES	None.	



VISUAL INSPECTION  
PHASE I  
EXHIBITION

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
JUNCTION OF EXHIBITION AND ABUTMENT, SPILLWAY AND DAM	No signs of distress.	
ANY NOTICEABLE SEEPAGE	Numerous wet areas on the downstream face and an area below the toe of the dam. See Plate 7 for locations.	
STAFF GAGE AND RECORDER	None.	
DRAINS	None.	

VISUAL INSPECTION  
PHASE I  
OUTLET WORKS

VISUAL EXAMINATION OF CRACKING AND SPALLING OF CONCRETE SURFACES IN OUTLET CONDUIT	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
	The outlet conduit was not accessible for inspection. Only the downstream end was visible. No distress was observed.	
INTAKE STRUCTURE	Visible portions are in good condition.	
OUTLET STRUCTURE	Riprapped plunge pool. In good condition.	
OUTLET CHANNEL	No obstructions in the outlet channel that would significantly affect the discharge capacity of the outlet works.	
EMERGENCY GATE	Lake drawdown sluice gate was operated by maintenance personnel and was observed to be functional.	

VISUAL INSPECTION  
PHASE I  
UNCATED SPILLWAY

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CONCRETE WEIR	The emergency spillway has no concrete overflow structure.	
APPROACH CHANNEL	Trapezoidal earth channel. In good condition.	
DISCHARGE CHANNEL	Trapezoidal earth channel. In good condition.	
BRIDGE AND PIERS	None.	



VISUAL INSPECTION  
PHASE I  
GATED SPILLWAY

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CONCRETE SILL	N/A.	
APPROACH CHANNEL	N/A.	
DISCHARGE CHANNEL	N/A.	
BRIDGE PIERS	N/A.	
GATES AND OPERATION EQUIPMENT	N/A.	

VISUAL INSPECTION  
PHASE I  
INSTRUMENTATION

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
MONUMENTATION/SURVEYS	None.	
OBSERVATION WELLS	None.	
WEIRS	None.	
PIEZOMETERS	None.	
OTHER	None.	

VISUAL INSPECTION  
PHASE I  
RESERVOIR  
OBSERVATIONS

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
SLOPES	Gentle to moderately steep. No significant shoreline erosion.	
SEDIMENTATION	Unknown.	
UPSTREAM RESERVOIRS	None.	



VISUAL INSPECTION  
PHASE I  
DOWNSTREAM CHANNEL

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CONDITION (OBSTRUCTIONS, DEBRIS, ETC.)	There are no obstructions that would affect the discharge capacity of the outlet conduit.	
SLOPES	No apparent instability (immediately downstream from the dam).	
APPROXIMATE NUMBER OF HOMES AND POPULATION	Two commercial buildings and one police station are located 3-1/2 miles downstream from the dam. The town of Falls Creek is located six miles downstream from the dam.	

**APPENDIX B**  
**CHECKLIST**  
**ENGINEERING DATA**  
**DESIGN, CONSTRUCTION, OPERATION**  
**AND HYDROLOGIC AND HYDRAULIC**  
**PHASE I**

# APPENDIX B

## CHECKLIST

### ENGINEERING DATA

#### DESIGN, CONSTRUCTION, OPERATION

##### PHASE I

NAME OF DAM Wolf Creek Dam

ID# NDI I.D. PA-748

DER I.D. 17-108

ITEM	REMARKS
AS-BUILT DRAWINGS	The drawings are available in the state files.
REGIONAL VICINITY MAP	See Plate 1.
CONSTRUCTION HISTORY	The dam was designed by R. M. Keddal and Associates, Inc., and Engineering Mechanics, Inc., of Pittsburgh, Pennsylvania in 1969. The dam was constructed by Canton Development Company with completion in July 1971.
TYPICAL SECTIONS OF DAM	See Plate 3.
OUTLETS - PLAN - DETAILS - CONSTRAINTS - DISCHARGE RATINGS	See Plates 4 and 6.



CHECKLIST  
ENGINEERING DATA  
DESIGN, CONSTRUCTION, OPERATION  
PHASE I

ITEM	REMARKS
RAINFALL/RESERVOIR RECORDS	Not available.
DESIGN REPORTS	Holf Creek Dam for Treasure Lake, Inc., prepared by R. M. Keddal and Associates, Inc., Engineers and Surveyors, and Engineering Mechanics, Inc., Consulting Engineers (the report is undated).
GEOLOGY REPORTS	None prepared.
DESIGN COMPUTATIONS HYDROLOGY & HYDRAULICS DAM STABILITY SEEPAGE STUDIES	Hydrology and hydraulic calculations and some preliminary stability analyses for the embankment are included in the above-referenced design report. No reference to any detailed stability analysis was found.
MATERIALS INVESTIGATIONS BORING RECORDS LABORATORY FIELD	Boring logs and the results of laboratory tests are included in the engineer's report.

**CHECKLIST  
ENGINEERING DATA  
DESIGN, CONSTRUCTION, OPERATION  
PHASE I**

ITEM	REMARKS
POST CONSTRUCTION SURVEYS OF DAM	None reported.
BORROW SOURCES	Unknown.
MONITORING SYSTEMS	None.
MODIFICATIONS	None.
HIGH POOL RECORDS	Not recorded.

CHECKLIST  
ENGINEERING DATA  
DESIGN, CONSTRUCTION, OPERATION  
PHASE I

ITEM	REMARKS
POST CONSTRUCTION ENGINEERING STUDIES AND REPORTS	None reported.
PRIOR ACCIDENTS OR FAILURE OF DAM DESCRIPTION REPORTS	None reported.
MAINTENANCE OPERATION RECORDS	Not recorded.
SPILLWAY PLAN SECTIONS DETAILS	See Plates 2 and 5.
OPERATING EQUIPMENT PLANS AND DETAILS	See Plates 4 and 6.



**CHECKLIST  
ENGINEERING DATA  
HYDROLOGIC AND HYDRAULIC**

**DRAINAGE AREA CHARACTERISTICS:** 4.4 square miles (woodlands)  
**ELEVATION; TOP NORMAL POOL AND STORAGE CAPACITY:** 1662.5 (3700 acre-feet)  
**ELEVATION; TOP FLOOD CONTROL POOL AND STORAGE CAPACITY:** 1670 (6700 acre-feet)  
**ELEVATION; MAXIMUM DESIGN POOL:** 1670  
**ELEVATION; TOP DAM:** 1670 (as designed); 1670.6 (low spot on crest)

**SPILLWAY: (Emergency Spillway)**

- a. Elevation 1664.5
- b. Type Trapezoidal open channel
- c. Width 130 feet (as measured perpendicular to flow direction)
- d. Length Not applicable
- e. Location Spillover Adjacent to emergency spillway
- f. Number and Type of Gates None

**OUTLET WORKS:**

- a. Type 15-inch reservoir drainpipe, 36-inch reinforced concrete conduit
- b. Location About 250 feet from left abutment
- c. Entrance Inverts Elevation 1643
- d. Exit Inverts Elevation 1637<sup>+</sup>
- e. Emergency Draindown Facilities 15-inch pipe

**HYDROMETEOROLOGICAL GAGES:**

- a. Type None
- b. Location None
- c. Records None

**MAXIMUM NONDAMAGING DISCHARGE:** Emergency spillway discharge capacity

**APPENDIX C**  
**PHOTOGRAPHS**


LIST OF PHOTOGRAPHS  
WOLF CREEK DAM  
NDI I.D. NO. PA-748  
APRIL 4, 1979

PHOTOGRAPH NO.

DESCRIPTION


1	Crest (looking north). Emergency spillway in foreground.
2	Emergency spillway approach channel.
3	Emergency spillway discharge channel.
4	Primary spillway intake structure and outlet pipe sluice gate control.
5	Primary spillway discharge pipe.
6	Wolf Run, approximately two miles downstream (stream behind pine trees).





Photograph No. 1

Crest (looking north). Emergency spillway in foreground.



Photograph No. 2

Emergency spillway approach channel.



Photograph No. 3  
Emergency spillway discharge channel.



Photograph No. 4  
Primary spillway intake structure and outlet pipe  
sluice gate control.



Photograph No. 5  
Primary spillway discharge pipe.



Photograph No. 6  
Wolf Run, approximately two miles downstream  
(stream behind pine trees).



**APPENDIX D**  
**CALCULATIONS**

HYDROLOGY AND HYDRAULIC ANALYSIS  
DATA BASE

NAME OF DAM: Wolf Creek Dam (NDI I.D. PA-425)

PROBABLE MAXIMUM PRECIPITATION (PMF) = 23.3 INCHES/24 HOURS<sup>(1)</sup>

STATION	1	2	3	4	5
Station Description	Treasure Lake	Wolf Creek Dam			
Drainage Area (square miles)	4.36	0			
Cumulative Drainage Area (square miles)	4.36	4.36			
Adjustment of PMF for Drainage Area (2) <sup>(2)</sup>					
6 Hours	117	-			
12 Hours	127	-			
24 Hours	141	-			
48 Hours	151	-			
72 Hours	-	-			
Snyder Hydrograph Parameters					
Zone (3)	24	24A	-		
$C_p/C_t$ (4)	0.45/1.6	0.45/4.2	-		
L (miles) (5)	2.1	-	-		
$L_{ca}$ (miles) (5)	0.5	-	-		
$t_p = C_t(L \cdot L_{ca})^{0.3}$ (hours)	1.62	4.26	-		
Spillway Data (6)		Pri- mary	Emer- gency		
Crest Length (ft)	-	18	130		
Freeboard (ft)	-	8.2	5.5		
Discharge Coefficient	-	-	-		
Exponent	-	-	-		

(1) Hydrometeorological Report 33 (Figure 1), U.S. Army, Corps of Engineers, 1956.

(2) Hydrometeorological Report 33 (Figure 2), U.S. Army, Corps of Engineers, 1956.

(3) Hydrological zone defined by Corps of Engineers, Baltimore District, for determining Snyder's Coefficients ( $C_p$  and  $C_t$ ). Zone 24A was recommended by the COE. However, conservative Zone 24 was used.

(4) Snyder's Coefficients.

(5) L = Length of longest water course from outlet to basin divide.

$L_{ca}$  = Length of water course from outlet to point opposite the centroid of drainage area.

(6) Flood discharge capacity was based on the combined capacity of the primary and emergency spillways of Wolf Creek Dam and Calion Bay Dam.

\*\*\*\*\*  
 FLOOD HYDROGRAPH PACKAGE (NEC-1)  
 DAM SAFETY VERSION JULY 1978  
 LAST MODIFICATION 26 FEB 79  
 \*\*\*\*\*

1	A1	SNYDER UNIT HYDROGRAPH, FLOOD ROUTING AND DAM OVERTOPPING ANALYSES							
2	A2	TREASURE LAKE (LAKE RENE DAM) CLEARFIELD CO. NDI-ID. PA426. PROJ. NO. 78-367-21							
3	A3	FOR 20%, 30%, 40%, 50%, 60%, 70%, 80%, 90%, AND 100% PMF							
4	B	300	0	10	0	0	0	0	-4
5	B1	5							0
6	J	1	9	1					
7	J1	0.20	0.30	0.40	0.50	0.60	0.70	0.80	0.90
8	K	0	1						1.00
9	K1								
10	M	1	4.36						
11	P	23.3	117	127	141	151			
12	T							1.0	.05
13	W	1.62	0.45						0.112
14	X	-1.0	-0.05	2.0					
15	K	1	2						
16	K1								
17	V								
18	V1	1							
19	Y41662.5	1663.0	1663.5	1664.6	1665.0	1665.2	1666.0	1668.0	1670.0
20	Y5	0.0	40.0	112.0	248.0	295.0	312.0	606.0	5297.0
21	\$S1000.0	4052.0	6087.0						15302.0
22	\$E1662.5	1670.0	1675.0						
23	\$S1662.5								
24	\$D1670.1	3.1	1.5	2130.0					
25	\$L215.0	365.0	430.0	530.0	630.0	730.0	980.0	1180.0	1230.0
26	\$V1670.1	1670.2	1670.4	1670.7	1670.8	1670.9	1671.0	1671.4	1671.7
27	K	99							

COMPUTER INPUT OVERTOPPING ANALYSIS

PAGE D2 of 4



PEAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS  
 FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)  
 AREA IN SQUARE MILES (SQUARE KILOMETERS)

OPERATION	STATION	AREA	PLAN	RATIOS APPLIED TO FLOWS								
				RATIO 1	RATIO 2	RATIO 3	RATIO 4	RATIO 5	RATIO 6	RATIO 7	RATIO 8	RATIO 9
				.20	.30	.40	.50	.60	.70	.80	.90	1.00
HYDROGRAPH AT	1	4.36	1	2170.	3255.	4340.	5425.	6510.	7596.	8681.	9766.	10851.
	(	11.29)	(	61.45)	( 92.18)	( 122.90)	( 153.63)	( 184.36)	( 215.08)	( 245.81)	( 276.53)	( 307.26)
ROUTED TO	2	4.36	1	279.	628.	1273.	1917.	2553.	3387.	4180.	4954.	5913.
	(	11.29)	(	7.91)	( 17.77)	( 36.66)	( 54.29)	( 72.28)	( 95.91)	( 118.36)	( 140.28)	( 167.63)

# SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1 .....	ELEVATION STORAGE OUTFLOW	INITIAL VALUE 1662.50 1000. 0.	SPILLWAY CREST 1662.50 1000. 0.	TOP OF DAM 1670.10 4093. 5497.					
RATIO OF PMF	MAXIMUM RESERVOIR W.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS		
.20	1664.87	0.00	1963.	779.	0.00	48.83	0.00		
.30	1665.88	0.00	2373.	628.	0.00	47.33	0.00		
.40	1666.64	0.00	2683.	1273.	0.00	46.00	0.00		
.50	1667.33	0.00	2966.	1917.	0.00	45.33	0.00		
.60	1668.01	0.00	3243.	2553.	0.00	45.17	0.00		
.70	1668.62	0.00	3489.	3387.	0.00	44.67	0.00		
.80	1669.19	0.00	3723.	4180.	0.00	44.50	0.00		
.90	1669.75	0.00	3951.	4954.	0.00	44.33	0.00		
1.00	1670.27	.17	4163.	5913.	2.00	44.17	0.00		

OVERTOPPING ANALYSIS SUMMARY

PAGE D4 of 4

# D'APPOLONIA

CONSULTING ENGINEERS, INC.

By NTC Date 4-18-79 Subject LAKE RENE Sheet No. 1 of 1  
 Chkd. By BE Date 4-19-79 SPILLWAY RATING Proj. No. 78-367-21

22  
23

## SPILLWAY RATING

{ TWO PRIMARY — 3'  $\phi$  PIPE W/SCS RISER @ ELEV 1662.5 <sup>(1)</sup>  
 { TWO EMERGENCY ROCK CUT SPILLWAYS { WOLF CREEK 130' @ 1665.2 <sup>(2)</sup>  
 { GALION BAY 26' @ 1664.6 <sup>(3)</sup>

ELEVATION. (RESERVOIR)	WOLF CREEK COMBINED SPILLWAY CAPACITY, cfs	GALION BAY COMBINED SPILLWAY CAPACITY, cfs	TOTAL CAPACITY FOR TREASURE LAKE cfs
1662.5	0	0	0
1663	20	20	40
1663.5	56	56	112
1664.6	124	124	248
1665	138	157	295
1665.2	139	173	312
1666	392	294	686
1668	1792	743	2535
1670	3844 <sup>TOP OF DAM</sup>	1453	5297
1675	10933	4369	15302

NOTE: FIGURES ROUNDED UP TO NEAREST . CFS.

$$(1) \text{ PRIMARY SPILLWAYS } \begin{cases} Q = 3.1(2L)H^{3/2} & L=9' \therefore Q = 55.8 H^{3/2} \\ \text{for } 0 < H < 1.5' \\ Q = C_d A_b \sqrt{2gH} & L_b = 207' \quad C_d = 0.5 \\ = 28.5 H^{1/2} & \text{for } H \geq 1 \end{cases}$$

$$(2) \text{ WOLF CR. EMER. SPILLWAY } \quad Q = 2.7 (130) H^{1.8}$$

$$(3) \text{ GALION BAY EMER. SPILLWAY } \quad Q = 2.7 (26) H^{1.8}$$



**APPENDIX E**  
**REGIONAL GEOLOGY**

## APPENDIX E REGIONAL GEOLGOY


Wolf Creek Dam is located on strata of the Allegheny Formation (Pennsylvanian Age). The site lies along the northwest flank of the Punxsutawney-Caledonia Syncline. Strata in the area dip gently to the southeast at about 100 feet per mile.

The Allegheny Formation consists primarily of thick-bedded to massive, coarse-grained sandstones and conglomerates. Thin coal seams and shales also exist.

The major coal seam in the area is the Upper Freeport which is the contact between the Allegheny Formation and the overlying Conemaugh Formation. This seam has been strip mined northwest and south of the dam. The Lower Freeport and Kittanning coals also exist in the area below the site. These coals are potential coking coals but have not been widely mined in the area.

One major fault exists in the area and is located approximately two miles northeast of the site. This fault is known as the Mountain Run Fault and trends to the northeast along the southeastern flank of the Boone Mountain Anticline. Maximum displacement along the fault is estimated to be 400 feet.

DRAWING 76 57-A34  
 NUMBER  
 CHECKED BY  
 APPROVED BY  
 ACS 5-29-79  
 DRAWN BY



STORAGE, WOLF CREEK, KYLE,  
 LAKE RENE, LAKE SABULA,  
 GALION BAY AND CLOE DAM

GEOLOGY MAP

REFERENCE  
 GEOLOGIC MAP OF PENNSYLVANIA PREPARED  
 BY COMMONWEALTH OF PENNA. DEPT. OF INTERNAL  
 AFFAIRS, DATED 1960, SCALE 1" = 4 MILES

DAIPTCDLONLA



DRAWN BY ACS 6-1-79 CHECKED BY JEF 6-4-79 APPROVED BY JHU 6-4-79 DRAWING NUMBER 78 7-A35

## PENNSYLVANIAN

### APPALACHIAN PLATEAU



#### Monongahela Formation

*Cyclic sequences of sandstone, shale, limestone and coal; limestone prominent in northern outcrop areas; shale and sandstone increase southward; commercial coals present; base at the bottom of the Pittsburgh Coal.*



#### Conemaugh Formation

*Cyclic sequences of red and gray shales and siltstones with thin limestones and coals; massive Mahoning Sandstone commonly present at base; Ames Limestone present in middle of sections; Brush Creek Limestone in lower part of section.*



#### Allegheny Group

*Cyclic sequences of sandstone, shale, limestone and coal; numerous commercial coals; limestones thicken westward; Vanport Limestone in lower part of section; includes Freeport, Killbuck, and Clarion Formations.*



#### Pottsville Group

*Predominantly sandstones and conglomerates with thin shales and coals; some coals mineable locally.*

### ANTHRACITE REGION



#### Post-Pottsville Formations

*Brown or gray sandstones and shales with some conglomerate and numerous mineable coals.*



#### Pottsville Group

*Light gray to white, coarse grained sandstones and conglomerates with some mineable coal; includes Sharp Mountain, Schuylkill, and Tumbling Run Formations.*

## MISSISSIPPIAN



#### Mauch Chunk Formation

*Red shales with brown to greenish gray flaggy sandstones; includes Greenbrier Limestone in Fayette, Westmoreland, and Somerset counties; Loyalhanna Limestone at the base in southwestern Pennsylvania.*



#### Pocono Group

*Predominantly gray, hard, massive, cross-bedded conglomerate and sandstone with some shale; includes in the Appalachian Plateau Raritan, Shenango, Cayahoga, Cassenago, Corru, and Knapp Formations; includes part of "Oswayo" of M. L. Fuller in Potter and Tioga counties.*

### GEOLOGY MAP LEGEND

#### REFERENCE:

GEOLOGIC MAP OF PENNSYLVANIA PREPARED BY COMMONWEALTH OF PENNA. DEPT. OF INTERNAL AFFAIRS, DATED 1960, SCALE 1" = 4 MILES

**D'APOLONIA**